



## 942 OLIVE PROJECT – BID ADDENDUM #1 – 10/9/2015

### NARRATIVE OF CHANGES TO DRAWINGS AND SPECIFICATIONS for BID SET DATED 9/25/2015

#### ARCHITECTURAL

##### G1.0 Cover

- Sheet A7.1 Interior Details added to index

##### G1.2 Assemblies

- 1/G1.2 Door Schedule; Several changes throughout
- 3/G1.2 Partition Assembly Types; New ceiling height elevation noted
- 4/G1.4 Ceiling Assembly Types; New ceiling height elevation noted

##### A1.1 Plan

- Note added about slab mounted painted steel guardrails at ramps in center of building
- Plan change at 'phone booths' H114
- Plan changes to mechanical (104B) and electrical (104C) rooms and exterior door vestibule adjacent to Flex Space 104
- Detail call-outs added that reference details on new sheet A7.1

##### A2.1 Furniture and Fixtures

- Plan and small changes shown at Phone Booths and Open Office area – see clouds.

##### A3.1 Ceiling Plan

- Revised ceiling heights noted at acoustic ceilings
- Plan changes at mechanical, electrical, and door vestibule adjacent to Flex Space 104
- Plan changes and notes at front entry
- See new notes about design mounting heights of light fixtures

**INTERIOR ELEVATIONS;** Please note that ALL sheets now show revised wall finish heights; 10' to top of wall finish typical for both OSB and clear corrugated plastic panels unless otherwise noted on drawings. Walls surrounding the Computer Lab and the 3D Printers/Polymer Lab still continue to underside of roof deck. ***ALSO – italicized entries below are duplicate entries because the pertinent information shows up on more than one page.***

##### A4.0 Interior Elevations

- 1/A4.0-B; Several changes showing new structural members and new notes

##### A4.1 Interior Elevations

- Frame at interior relite at Large Conference room changed to anodized aluminum storefront and height of glazing and door have changed. 1/A4.1-A & 3/A4.1-C. See new Interior storefront glazing schedule on A4.6

##### A4.2 Interior Elevations

- Changes to wall materials around Computer Lab; See **3/A4.2-A** and 2/A4.3-B
- 1/A4.2-B; See note on 1/A4.4-H about solid wood blocking between extended white board panels at each side.
- 2/A4.2-D; Added note about replacing boarded up openings in garage door with glass as part of base bid.

#### A4.3 Interior Elevations

- *Changes to wall materials around Computer Lab; See 3/A4.2-A and 2/A4.3-B*
- Clear / square window openings into 3D Printers/Polymer Shop are now tempered glass; See **1C&D/A4.3 and 2B/A4.3** and 1/A4.4 and 1/A4.4-A
- 2/A4.3-B; Added note about metal corner guard
- Changes to wall materials in 3D Printers/Polymer Shop. See 1/A4.3-C & D

#### A4.4 Interior Elevations

- *Clear / square window openings into 3D Printers/Polymer Shop are now tempered glass; See 1&2/A4.3 and 1/A4.4 and 1/A4.4-A*
- 1/A4.4-A; Added note about metal corner guard
- Sheet A4.4; Added notes about ceiling type – see clouds

#### A4.5 Interior Elevations

- Frames at interior relite windows at Offices 1 & 2 adjacent to Hoteling / Co-Working space #114 changed to anodized aluminum storefront. 3/A4.5-B. See new Interior storefront glazing schedule on A4.6
- 2/A4.5-C; Shows new structural members and new phone booth configuration

#### A4.6 Interior Elevations

- See new Interior storefront glazing schedule. Elevations just show revised wall panel heights.

#### A5.1 Enlarged Plan

- 2,3,4,& 5/A5.1 Changes shown to Phone Booths

#### A5.2 Enlarged Plan

- 1 & 2 /A5.2; Changes shown to South Entry Vestibule
- 3 / A5.2; See new note regarding opening in masonry wall at West Entrance
- 4 / A5.2 Enlarged Floor Plan at West Entry; Changes to wall of Computer Lab shown.

#### A5.3 Enlarged Plan

- 2/A5.3 Section at East Entry; See revised notes

#### A6.0 Exterior Elevations

- 1/A6.0 South / Broadway Alley Elevation; See revised notes on drawing and in Exterior Elevation Notes

#### A7.1 Interior Details

- New sheet

### ELECTRICAL

#### E0.0 Cover Page

- Abbreviations; See clarifications and additions

#### E2.0 Lighting

- See clouded changes at main east entry and at mech/elec spaces near Flex Space 104

#### E3.0 Power

- See clouded changes along south wall from main east entry to south vestibule at exterior doors. Main electrical power for building is now routed under the floor slab and the electrical and mechanical rooms have been reconfigured to accommodate this change.
- See clouded changes at West Entry door area – deleting an exterior GFI outlet
- See clouded changes showing new location for outlets in 3D Printing & Polymer Lab.

#### E5.0 Diagrams, Schedules and Enlarged Plans

- See clouded changes